

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-163-20,214-00-00

LEASE NAME McClellan

WELL NUMBER #4

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 8 TWP. 9 RGE. 19 (E) or (W)

COUNTY Rooks

Date Well Completed 08/07/69

Plugging Commenced 12/20/02

Plugging Completed 12/23/02

RECEIVED
12-30-02
DEC 30 2002

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

KCC WICHITA

LEASE OPERATOR Palomino Petroleum, Inc.

ADDRESS 4924 SE 84th Street, Newton, KS 67114-8827

PHONE (316) 799-1000 OPERATORS LICENSE NO. 30742

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on December 20, 2002 (date)

by Richard Williams (KCC District Agent's Name).

Is ACO-1 filed? Unknown If not, is well log attached?

Producing Formation Depth to Top 3412' Bottom 3494' T.D. 3505'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0'	206'	8-5/8"	206'	0'
	Production	0'	3495'	5-1/2"	3495'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Perf well @ 1895', 1470', & 795'. Run tubing in to 2500', spot 100sx cement w/300# hulls. Pull well up to 1500', spot 125sx cement w/200# hulls. Pulled tubing out. Tied onto 5-1/2" spot 70sx cement and had 700#psi. Shut in @ 400#psi. Tied onto 8-5/8" spot 50sx cement & had 300#psi. Shut in @ 200#psi. Tore down and moved off.

Name of Plugging Contractor D.S. & W. Well Servicing, Inc. License No. 6901

Address P.O. Box 231, Claflin, KS 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Palomino Petroleum, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

KAREN J. MITCHELL
Notary Public - State of Kansas
My Appt. Expires 4/13/06

(Signature) Edward S. Nemnich
(Address) P.O. Box 231, Claflin, KS 67525

SUBSCRIBED AND SWORN to before me this 26th day of December, 2002

My Commission Expires: April 13, 2006

Notary Public

OR