

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-20,222-00-00

LEASE NAME McClellan

WELL NUMBER #5

330 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 8 TWP. 9 RGE. 19 (E) or (W)

COUNTY Rooks

Date Well Completed 08/07/69

Plugging Commenced 12/19/02

Plugging Completed 12/23/02

DEC 30 2002
12-30-02

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Palomino Petroleum, Inc.

ADDRESS 4924 SE 84th Street, Newton, KS 67114-8827

PHONE# (316)799-1000 OPERATORS LICENSE NO. 30742

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on December 20, 2002 (date)

by Richard Williams (KCC District Agent's Name).

Is ACO-1 filed? Unknown If not, is well log attached? _____

Producing Formation _____ Depth to Top 3390' Bottom 3418' T.D. 3525'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0'	205'	8-5/8"	205'	0'
	Production	0'	3522'	5-1/2"	3522'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Bottom plug. Sand well back to 3270', spot 5sx cement. Perf well @ 1915, 1490' & 815'. Run tubing in to 2500', spot 100sx cement w/300# hulls. Pull up to 1000' spot 120sx cement w/300# hulls. Pull tubing out. Tied onto 5-1/2", spot 50sx cement w/400#psi. Shut in @ 100#psi. Tied onto 8-5/8", spot 50sx cement w/200# hulls w/400#psi. Shut in @ 200#psi. Tore down and moved off.

Name of Plugging Contractor D.S. & W. Well Servicing, Inc. License No. 6901

Address P.O. Box 231, Claflin, KS 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Palomino Petroleum, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Edward S. Nemnich

KAREN J. MITCHELL
Notary Public - State of Kansas
My Appt. Expires 4/13/06

(Address) P.O. Box 231, Claflin, KS 67525

SUBSCRIBED AND SWORN TO before me this 26th day of December, 2002

Karen J. Mitchell
Notary Public

My Commission Expires: April 13, 2006

OR