

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Tony Martin of Abercrombie Dily, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Ed. Druling

Complete Address: 2908 Barclay Dr. Hays, Kans 67601

Lease Name: St. Peter Well No. #2

Location: SE-SE-SW Sec. 17 Twp. 9^S Rge. 19^W (E) (W)

County: Roos Total Depth: 3584^{EE}

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Martin was instructed to plug the well as follows:

8 5/8" 265^{EE} SR. CUC. w/ 175^{SE} Common - 2% Gel. - 2 1/2% Co-cl.

Order: 110^{SE} 50/50 Pozmin 6% Gel. & 8 5/8" Plug (Elev. 2199⁴⁸)

Spot with Drill Stem - with Heavy Mud Between all Plug.

1^{SE} Plug @ 800^{EE} w/ 70^{SE} Cont.

2^{NE} Plug @ 240^{EE} w/ 25^{SE} Cont.

3^{NE} Plug - Solid Bridge @ 40^{EE} 1/0 w/ 10^{SE} Cont.

5^{SE} Rat Hole

Very truly yours (By Sam Cont)

1/12/81
JAN 12 1981

CONSERVATION DIVISION
WICHITA, KANSAS

Samuel Schmidt
Conservation Division Agent