

15-163-20276-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
10/15/74
OCT 15 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Kathol Petroleum Company
Complete Address 230 Sutton Place, Wichita, Kansas
Lease Name Marcotte Well No. 1
Location SE SE SW Sec. 18 Twp. 9 Rge. (E) (W) 19
County Rooks Total Depth 3556'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Co Tools
Address License No. 661
Operation Completed: Hour 11:30 A Day 12 Month 10 Year 1974

The above well was plugged as follows:

Total Depth 3556' 8 5/8 csg set at 206' cwc 150 sx.
5 1/2 csg set at 3545' cw 150 sk. with perf. (3277-3520)
5 1/2 csg plg'd at 1800' -dumped 4 sk cem W/dump bailer. (1800-1770)
Cutoff & recovered 1200' of 5 1/2 csg.
Pumped down 8 5/8 csg with 20 sk gel & water -100 lbs hulls -70 sk 50-50 poz 6% -
10 sk gel & water -released 8 5/8 plug & pumped 50 sx 50-50 poz 6% by Allied.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 10/16/74
INV. NO. 106-W