


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County, Sec. 18 Twp. 9S Rge. 21W (X) (W)
Location as "NE/CNW%SW%" or footage from lines 990'N-330'E of Center
Lease Owner Cities Service Oil Company
Lease Name Seefeld Well No. 6
Office Address Box 553, Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed 11-16-19 50
Application for plugging filed 8-27-19 63
Application for plugging approved 8-28-19 63
Plugging commenced 9-11-19 63
Plugging completed 9-11-19 63
Reason for abandonment of well or producing formation Non Commercial

If a producing well is abandoned, date of last production 1-3-63 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. I. Nichols, Morland, Kansas
Producing formation Arbuckle Depth to top _____ Bottom _____ Total Depth of Well 3843 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	@240'	0
				5-1/2"	@3840'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with sand and cement to 3818';
Put rubber plug and rock bridge at 600';
Spotted 10 sx. cement through tubing at 600' by Halliburton;
Put in rock bridge;
Spotted 10 sx. of cement through tubing at 240' by Halliburton;
Pushed Howco rubber plug to 35';
Filled hole from 35' to base of cellar with 5 sx. cement.
Job complete at 3:00 P.M., 9/11/63.

RECEIVED
STATE CORPORATION COMMISSION

SEP 20 1963
9-20-63

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Peel Drilling Company Halliburton Cementing Co.
Address Hoisington, Kansas Hays, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
M. M. Hardin (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. M. Hardin
M. M. Hardin - District Superintendent
Box 553, Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 19th day of SEPT, 19 63

My commission expires DEC. 6, 1966 CMMcAuland Notary Public.

C O P Y

WELL RECORD

WILDCAT.....

DISCOVERY.....

POOL.....

COMPANY Cities Service Oil Co. WELL # 6 FARM Seefeld

LOCATION 990' North and 330' East of Center Sec. 18-T9-R21W

ELEV. 2308' (2305' Gr.) CO. Graham STATE Kansas

IP. Physical Potential: 167 oil, 26% water, 24 hrs. (12-26-50)

PERFS.....

FRAC..... ACID None

T.D. 3843' PBTD..... GRAV/GOR.....

DRLG. COMM. November 8, 1950 COMP. November 16, 1950 CONTRACTOR R.W. Rine Drilling Co.

CASING RECORD:

8-5/8" @ 240' cem. 175 sx. cement and 200#C.C.
5-1/2" @ 3840' cem. 175 sx. cement

FORMATION RECORD:

surface clay	0-40
sand & lime	240
shale, sand and shells	1810
anhydrite	1845
shale and shells	2685
lime and shale	3545
lime	3810
lime and chert	3841
3841 RTD = 3843 SIM	

Drill stem test 3837-3841, recovered
430' oil and 30' oil-cut mud in 30
minutes, BHP 1040#.

corr. Top Lansing	3527'
corr. Top Conglomerate	3811'
corr. Top Simpson Sand	3828'
corr. Top Simpson shale	3830'
corr. Top Arbuckle	3838'
Penetration	5'
Total Depth	3843'

Fillup:

150' oil in 35 minutes
410' oil in 1-1/4 hrs.
740' oil in 1 hr. 50 minutes
1560' oil in 3-1/2 hrs.
1860' oil in 4 hrs. 35 minutes
2805' oil in 15 hrs.

SYFO:	500'	1°
	1000'	0°
	1500'	0°
	2000'	0°
	2500'	1°

7-7/8" rotary hole.

RECEIVED
STATE CORPORATION COMMISSION

SEP 20 1963

CONSERVATION DIVISION
Wichita, Kansas