

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-005-01441-00-00

API NUMBER 10-22-55

LEASE NAME Sutor B

WELL NUMBER 9

SPOT LOCATION NE NE SE

SEC. 18 TWP. 9 RGE. 21 (E) (W)

COUNTY Graham

Date Well Completed 10-22-55

Plugging Commenced 5-8-90

Plugging Completed 5-8-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Okmar Oil Company

ADDRESS Box 723 Hays, Kansas 67601

PHONE # (913) 628 6101 OPERATORS LICENSE NO. 5245

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3804

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	150	8 5/8		None
	Casing	0	3800	5 1/2		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Trip in with openended tubing to 2113.28. Mix 50 sks. 65/35 pos. 10% gel followed by 50 sks. common with 300# hulls. Pulled 32 its. to 1105.46'. Mix 80 sks. 65/35 pos. 10% gel, 150# hulls. Circulate cement to surface. TOH with tubing. Hook to 8 5/8. Mix 5 sks. 65/35 pos. 10% gel, 500#. Hook to 5 1/2 and mix 85 sks. 65/35 pos. 10% gel. 500# max. Shut in 100#.

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Okmar Oil Company License No. 5245
Address Box 723 Hays, Kansas 67601

BJ Services- cement

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ted Crawford
(Address) Box 723 Hays, KS 67601



SUBSCRIBED AND SWORN TO before me this 9 day of May, 1990

Rosemary Smith
Notary Public

My Commission expires: 5/1/1991

5-10-90

Form CP-4
Revised 06-83