

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-065-01436-00-00

API NUMBER _____

LEASE NAME Sutor B

WELL NUMBER 3

SPOT LOCATION SE NE SE

SEC. 18 TWP. 9 RGE. 21(E) or (W)

COUNTY Graham

Date Well Completed _____

Plugging Commenced 5-9-90

Plugging Completed 5-9-90

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Okmar Oil Company

ADDRESS Box 723 Hays, Kansas 67601

PHONE # (913) 628 6101 OPERATORS LICENSE NO. 5245

Character of Well SWD
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas 67601

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3796

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	157	8 5/8		None
	Casing	0	3794	5 1/2		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Perf. 2 holes at 1785' and 2 holes at 1030' TIF with 67 jts. openended to 2113.26. Mix 50 sks. 65/35 pos; 10% gel, followed by 50 sks. common with 250# hulls through out. Pull 32 jts. to 1105.46. Mix 80 sks. 65/35 pos, 10% 150# hulls. Circulate to surface. Hook to 8 5/8 and mix 75 sks. 65/35 pos, 10% 50# hulls. Shut in 100#. Hook to 5 1/2 mix 70 sks. 65/35 box, 10% gel, 100# hulls. Shut in 250#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Okmar Oil Company License No. 5245

Address Box 723 Hays, Ks. 67601

B.I. Services- cementer

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ted Crawford

(Address) Box 723 Hays, Ks. 67601

ROSEMARY SMITH
 NOTARY PUBLIC
 STATE OF KANSAS
 MY APPT. EXP. MAY 1, 1991

SUBSCRIBED AND SWORN TO before me this 12 day of May, 1990

Rosemary Smith
 Notary Public

My Commission expires: 5-1-1991

MAY 14 1990
 5-14-90
 CONSERVATION DIVISION
 Wichita, Kansas

Form CP-4
 Revised 06-83