


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 18 Twp. 9S Rge 21 (E) x(W)
Location as "NE/CNW/SW" or footage from lines C SW NE NE
Lease Owner Cities Service Oil Co.
Lease Name Seefeld Well No. 8D
Office Address 209 E. William, 700 Sutton Pl. Bldg. Wichita, KS 67202
Character of Well (completed as Oil, Gas or Dry Hole) Salt Water Disposal
Date well completed 2/23 19 52
Application for plugging filed 7/11 19 74
Application for plugging approved 7/12 19 74
Plugging commenced 8/6 19 74
Plugging completed 8/6 19 74
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Arbuckle Depth to top 3847 Bottom 4253 Total Depth of Well 4257 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	237'	None
				7"	3847'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged. Pump 50 sacks cement, 40 sacks gel, 2 sacks hulls, 100 sacks cement, 1 sack hulls. Minimum pressure 200 psi, maximum 1000 psi. SIP 1000 psi.

RECEIVED
STATE CORPORATION COMMISSION
AUG 22 1974
8-22-74
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Halliburton (If additional description is necessary, use BACK of this sheet)
Address Hays, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.
E. W. Peterman

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *E. W. Peterman*

209 E. William, 700 Sutton Pl. Bldg. Wichita, KS (Address) 67202

SUBSCRIBED AND SWORN to before me this ninth day of August, 19 74

Glenn E. Meier

Notary Public.

My commission expires 6/3/77

WELL RECORD

Company Cities Service Oil Co. Well No. 8 Farm Seefeld S. W. D.
 Location 990' South and 990' West of NE Corner Sec. 18 T. 9 R. 21W
 Elevation 2260 (2257 Gr.) County Graham State Kansas
 Drlg. Comm. January 8, 1952 Contractor R. W. Rine Drilling Company
 Drlg. Comp. February 23, 1952 Acid None
 T. D. 4257' Initial Prod. Input Test: Ind. Cap. 7,400 bbls. per day (3-24-52)

CASING RECORD:

10-3/4" @ 237' cen. 200 sx cen. & 200# C. C.
 7" @ 3847' cen. 175 sx cen.

D-V tool at 1766' w/ 275 sx cement and 35 sx Stratacrete.

FORMATION RECORD:

clay	0-20
clay, shale & sand	238
shale, shells & sand	1185
shale & shells	1750
anhydrite	1795
shale & shells	2225
shale & lime streaks	2400
shale & lime	2520
lime	2620
shale & lime	2830
lime & shale	2925
lime	3060
lime & shale	3430
lime	3780
lime & chert	3810
lime	3850
lime	3887
shale	3889
lime	4184
sand	4235
Granite Wash	4257 T. D.

3850 RHD = 3847 SIM

Corr. Lansing	3470'
Corr. Conglomerate	3743'
Corr. Arbuckle	3769' (-1512)
Reagan	4184' (-1921)
Granite Wash	4235'
Penetration	22'
Total Depth	4257'

Input test at 4026' indicated capacity 7,400 bbls. per day..

SYFO: 500' 0°
 1000' 0°
 1500' 1°
 2000' 0°
 2500' 1°
 3000' 1°
 3500' 1°
 3725' 1°

8-3/4" rotary hole.

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 12 1954
 CONSERVATION DIVISION
 Wichita, Kansas