


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

GRAHAM COUNTY, KANSAS County. Sec. 29 Twp. 9S Rge. 21W (E)____(W)
Location as "NE/CNW/SW" or footage from lines SW SE NW
Lease Owner K & E DRILLING, INC.
Lease Name SMITH 'A' LEASE Well No. 1
Office Address 719 Union Center Bldg, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed 1-29-58 19____
Application for plugging filed 1-29-58 19____
Application for plugging approved 1-29-58 19____
Plugging commenced 1-29-58 19____
Plugging completed 1-29-58 19____
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius, Box 731, Hill City, Ks.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3942' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	249'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy mud to 600' Set solid bridge with 20 sx cement through drill pipe. Filled with heavy mud to 260' Set solid bridge with 15 sx cement through drill pipe. Filled with heavy mud to 40' Set solid bridge with 10 sx to base to cellar. Job Complete 1-29-58.

2/11/58

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor K & E DRILLING, INC.
Address 719 Union Center Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Dale Silcott (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott
Dale Silcott of K & E DRILLING, INC.
719 Union Center, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of February, 1958.

My commission expires 11 August 1958.

Patricia M. Edwards, Notary Public.

PLUGGING
FILE SEC. 29 T 9 R 21W
BOOK PAGE 79 LINE 40

DRILLER'S LOG

OPERATOR: K & E DRILLING, INC.
719 Union Center Building
Wichita 2, Kansas

FARM NAME: #1 SMITH 'A' LEASE

LOCATION: SW SE NW,
Sec. 29-98-21W
Graham Co, Kansas

CONTRACTOR: K & E DRILLING, INC.
719 Union Center Building
Wichita 2, Kansas

COMMENCED: 1-22-58
COMPLETED: 1-29-58

CASING: 8-5/8" @ 249' (160 sx)

ELEVATION: 2342' KB
PRODUCTION: D & A

R.T.D. 3942'

FORMATION RECORD

Shale	60
Sand	70
Shale	735
Sand & Shale	1250
Shale	1270
Sand	1560
Shale	1810
Anhydrite	1848
Shale & Shells	2165
Shale & Lime	2630
Lime & Shale	2800
Shale & Lime	3020
Lime & Shale	3210
Shale & Lime	3370
Lime	3532
Shale	3540
Lime & Shale	3590
Lime	3845
Lime & Shale	3907
Conglomerate	3942
R.T.D.	3942

CERTIFICATION

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

I, Dale Silcott of K & E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the #1 SMITH 'A' well.

Dale Silcott

Dale Silcott

Subscribed and sworn to before me this 4th day of February, 1958.

Patricia M. Edwards

Patricia M. Edwards, Notary Public

My commission expires: 11 August 1958.

PLUGGING
HET. SEC. 29T. 9. R21. W
BOOK PAGE 79 LINE 40