


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SE/SW" or footage from lines Graham County, Sec. 29 Twp. 9 Rge. 21 (E) (W)
Lease Owner Rains & Williamson Oil Company
Lease Name Karst #1 Well No. _____
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 2/24/72 _____ 19____
Plugging completed 2/26/72 _____ 19____
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3878' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	234	none
				5 1/2"	3873'	1584'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, sanded hole to 3850', set 5 sacks of cement.
Loaded casing with water, shot pipe at 1983', 1888', 1792', 1697',
1600', pulled 49 joints. Pumped 5 sacks hulls, 30 sacks gel and
100 pos mix, 6% gel.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
APR 11 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE,
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

Subscribed and Sworn to before me this 28th day of Feb., 19 72

My commission expires Feb. 15, 1975
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

ROTARY DRILLING LOG

Operator: Rains & Williamson Oil Co., Inc.
KARST #1
NE SW NW Sec. 29-9S-21W
Graham County, Kansas

Contractor: Rains & Williamson Oil Co., Inc.
Commenced: 12-14-68
Completed: 12-23-68 (Rotary)
Casing: 8-5/8"/234'/160 sx.
5-1/2"/3873'/150 sx.

Formations

Surface Clay	40'
Sand	105'
Shale	440'
Shale and Sand	1320'
D. Sand	1550'
Shale and Red Bed	1808'
Anhydrite	1845'
Shale	2125'
Shale and Lime	2515'
Lime and Shale	2680'
Shale and Lime	3280'
Lime and Shale	3535'
Lime	3830'
Lime and Chert	3878'
Rotary Total Depth	3878'


RECEIVED
STATE CORPORATION COMMISSION
JAN 14 1972
CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.

Wilson Rains
Wilson Rains

Subscribed and sworn to before me, a Notary Public within and for the State of Kansas, County of Sedgwick, this 27 day of December, 1968.



Sherry Gish
Sherry Gish Notary Public

My Commission Expires:
June 30, 1971