


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Graham County. Sec. 30 Twp. 9 Rge. 21W (E) (W)
Location as "NE/CNW/SW" or footage from lines NW NW NE
Lease Owner C-G Drilling Co. & Oil Trading Associates
Lease Name Lena Smith Well No. 1
Office Address 107 Rule Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 24 19 58
Application for plugging filed April 24 19 58
Application for plugging approved April 24 19 58
Plugging commenced April 25 19 58
Plugging completed April 25 19 58
Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3944 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	194.67'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 550'. Set plug. Put in 25 sacks cement. Filled to 190'. Set plug. Put in 1/2 sack hulls and 15 sacks cement. Filled with heavy mud up to 40'. Set plug. Filled to top with 1/2 sack hulls and 10 sacks cement.

4/29/58


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G Drilling Co.
Address 107 Rule Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
G. F. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway
107 Rule Building
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of April, 1958
My commission expires May 20, 1959
Vicky Jacobs
Vicky Jacobs Notary Public.



PLUGGING
FIL. SEC. 30 TWP. 9 RGE. 21W
BOOK PAGE 96 LINE 44

CONTRACTOR'S WELL LOG

OPERATOR C-G Drilling Co. & Oil Trading Associates WELL NAME Lena Smith #1
 LOCATION NW NW NE SEC. 30-9-21W RIG NO. 1
 COUNTY Graham STATE Kansas
 COMMENCEMENT DATE April 16, 1958 COMPLETION DATE April 24, 1958

LOG OF WELL

Elevation 2344' rotary bushing.
 All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	194	Shale-Sand		
194	790	Shale-Sand		
790	1050	Shale-Sand		
1050	1275	Sand		
1275	1450	Shale-Sand		
1450	1600	Shale-Sand		
1600	1856	Red Bed		
1856	1894	Anhydrite		
1894	1900	Shale-Shell		
1900	2058	Shale-Shell		
2058	2370	Shell-Shale		
2370	2580	Shale-Shell	0° - 2500	
2580	2705	Shale-Lime		
2705	2830	Lime-Shale	0° - 2750	
2830	2920	Lime-Shale		
2920	3015	Lime-Shale	0° - 3000	
3015	3200	Lime-Shale		
3200	3320	Shale-Lime	0° - 3250	
3320	3400	Shale-Lime		
3400	3480	Lime-Shale		
3480	3593	Lime-Shale		
3593	3634	Lime		
3634	3676	Lime-Shale		
3676	3728	Lime		
3728	3765	Lime		
3765	3792	Lime-Shale		DST 3738-3765'
3792	3871	Lime		
3871	3920	Lime		
3920	3944	Lime-Shale		

APR 29 1958
 DIVISION

CASING LEFT IN HOLE AFTER COMPLETION

Ran 194.67' (10 jts.) 8-5/8" OD Surface Casing.

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By *[Signature]*

SUBSCRIBED AND SWORN TO BEFORE ME THIS 28th day of April, 1958.

[Signature]
 Vicky Jacobs, Notary Public

My commission expires: May 20, 1959

