


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 30 Twp. 9 Rge. 21 (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines NW NW SW
Lease Owner Sunray Oil Corporation
Lease Name W. H. Smith Well No. 1
Office Address Box 195, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed May 20 19 50
Application for plugging filed May 20 19 50
Application for plugging approved 19
Plugging commenced May 20 19 50
Plugging completed May 20 19 50
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Petty
Producing formation Depth to top Bottom Total Depth of Well 3952 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Dry	3322	3352	8-5/8"	210'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3952-201'; set bridge plug @ 200' & dumped 15 sax cement on plug. Heavy mud from cement to 45'. Set plug at 45'. Capped well with 15 sax cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Sunray Oil Corporation
Address Box 195, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

W. R. Yinger (employee of owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) W. R. Yinger Engineer

Box 195, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 22nd day of May, 1950.

My commission expires April 19, 1952.

Notary Public



MAY 23 1950
5/23/50

SMITH WELL #1

Casing Record:
8" - 218'

COMPANY: Sunray Oil Corp.

CONTRACTOR: Aylward Drilling Co.

COMMENCED: May 7, 1950
COMPLETED: May 20, 1950

Description:
NW $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ of Section
30-98-21W, Graham Co., Kans.

Elevation:
Production: D. & A.

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Clay	0	70	
Sand	70	90	
Shale	90	1170	
Sand	1170	1210	Set 8" casing at 218'
Shale and Lime shells	1210	1295	
Sand	1295	1420	
Sand and shells	1420	1585	
Lime and shale	1585	1700	
Shale and shells	1700	1715	
Shale	1715	1815	
Red pod	1815	1828	
Anhydrite	1828	1865	
Lime and Shale	1865	2720	
Shale and shells	2720	2830	
Lime and shale	2830	3070	
Shale and lime shells	3070	3160	
Lime	3160	3275	
Shale and lime	3275	3469	
Lime and chalk	3469	3487	
Chert and lime	3487	3499	
Lime	3499	3523	
Shale	3523	3559	
Lime	3559	3694	D.S.T. 3604-13' Recovered 180' water.
Lime and shale	3694	3710	
Lime	3710	3789	
Shale	3789	3819	
Lime and shale	3819	3866	
Lime	3866	3872	
Conglomerate	3872	3893	
Shale	3893	3903	
Shale and chert	3903	3917	
Conglomerate & chert	3917	3932	
Arbuckle Limer	3932	3952	

T.D. 3952'

RECEIVED
Conservation Div.
MAY 27 1950
STATE CORPORATION
COMMISSION
KANSAS

TOPS:
Heabner 3523'
Lansing - K.C. 3559'
Base K.C. 3788'
Marston 3849'
Conglomerate 3872'
Arbuckle 3922'

I certify that this is a true and correct copy of the above log to the best of my knowledge.

Al Stalsky
Al Stalsky

Subscribed and sworn to before me this 22nd day of May, 1950.

Harold Cooper
NOTARY PUBLIC

PLUGGING
FILE SEC 30 T 9 R 20
BOOK PAGE 7 LINE 15

My commission expires
July 16, 1952.