


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Graham County, Sec. 30 Twp. 9S Rge. 21E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
E 1/2 SE NE

Lease Owner M.D. Weilert Oil  
Lease Name Smith Well No. 1  
Office Address Box 988 Hays, Kansas 67601  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole



Locate well correctly on above  
Section Plot

Date Well completed 7-30 1981  
Application for plugging filed 7-30 1981  
Application for plugging approved 7-30 1981  
Plugging commenced 7-30 1981  
Plugging completed 7-30 1981  
Reason for abandonment of well or producing formation  
Dry hole

If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3905'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	183'	8 5/8"	183	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1st Plug set at 950' with 60 sacks common cement 50-50 poz 6% gel

2nd Plug set at 200' with 30 sacks common cement 50-50 poz 6% gel

3rd Plug set at 40' with 10 sacks common cement 50-50poz 6% gel

5 sacks in rathole

10 min. circulating with drill mud

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oilwell Cementing

STATE OF Kansas COUNTY OF Graham, ss.  
Jerry M. Helberg (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)


*Jerry M. Helberg*  
Morland, Kansas 67650  
(Address)

SUBSCRIBED AND SWORN TO before me this 13 day of August, 1981

My commission expires 12-4-83

RECEIVED  
STATE CORPORATION COMMISSION  
8/14/81  
AUG 14 1981

CONSERVATION DIVISION  
Wichita, Kansas



15-065-2145B-00-00

DRILLERS LOG

SMITH # 1

CASING RECORD:

8 5/8" set at 183'

TOTAL DEPTH:

3905'

DESCRIPTION:

E 1/2 SE NE  
Sec. 30, Twp. 9S, Rge. 21W

OPERATOR: M.D. Weilert Oil

CONTRACTOR: Helberg Oil Company

COMMENCED: July 21, 1981

COMPLETED: July 30, 1981

FORMATION	TO	FROM	REMARKS
Sand	0	231	
Sand & Shale	231	473	
Shale	473	865	
Sand & Shale	865	1752	
Shale	1752	1817	
Anhydrite	1817	1854	
Shale	1854	2035	
Shale	2035	2269	
Shale	2269	2434	
Shale	2434	2564	
Shale	2564	2659	
Shale	2659	2806	
Lime & Shale	2806	3033	
Lime & Shale	3033	3145	
Lime & Shale	3145	3258	
Lime & Shale	3258	3311	
Lime	3311	3380	
Lime	3380	3468	
Lime & Shale	3468	3549	
Lime	3549	3618	
Lime	3618	3694	
Lime	3694	3725	
Lime	3725	3768	
Lime	3768	3832	
Lime	3832	3875	
Lime	3875	3905	
T.D.	3905		

D. & A.

I certify that the above is a true and correct copy of the log to the best of my knowledge.

Helberg Oil Company

*Jerry M. Helberg*  
Jerry M. Helberg

Subscribed and sworn to before me this 13 day of August, 1981.

RECEIVED  
STATE CORPORATION COMMISSION

*James Schmitt*  
Notary Public

CONSERVATION DIVISION  
Wichita, Kansas

My commission expires 12-4-83

