


15-163-00490-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rocks \_\_\_\_\_ County. Sec. 32 Twp. 9 Rge. (E) 18 (W)  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines SW NW NE  
Lease Owner Graham-Messman-Rinehart Oil Company  
Lease Name Stucky "A" Well No. 1  
Office Address 1005 E. Second Street, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 19, 19 53  
Application for plugging filed March 19, 19 53  
Application for plugging approved March 23, 19 53  
Plugging commenced March 20, 19 53  
Plugging completed March 20, 19 53  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19 \_\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty, Box 326, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3755 Feet  
Show depth and thickness of all water, oil and gas formations. 3760 KCC  
ZAP

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	170	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud to 160 ft.  
Bottom Plug @ 160 ft.  
w/  $\frac{1}{2}$  sk. hulls & 15 sx. cement. Top plug @ 40 ft.  
w/  $\frac{1}{2}$  sk. hulls & 10 sx. cement  
Mud to Surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graham-Messman-Rinehart Oil Company  
Address 1005 E. Second Street, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, SS.  
J. A. Gilliland (employee of owner) or (owner or operator)

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *J. A. Gilliland*  
1005 E. Second Street, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of March, 1953

*Barbara J. Scott*  
Notary Public.

My commission expires December 1, 1956

23-8390-s 6-51-20M

PLUGGING  
FILE SEC 32 T 9 R 18h  
BOOK PAGE 86 LINE 12

3/27/53

STUCKY "A" #1

WELL RECORD

Location: SW NW NE 32-9-18W  
Rocks County, Kansas

Operator: G-M-R Oil Company

Contractor: G-M-R Drilling Company

Casing Record: 8 5/8" @ 170' w/100 sx.

Commenced: March 11, 1953

Completed: March 19, 1953

Elevation: 2167 K.B.

Production: D & A

L O G

Sod & Sand 50  
Blue Shale 160  
Shale & Shells 900  
Shale 1050  
D. Sand 1227  
Shale & Sand 1491  
Shale 1563  
Anhydrite 1602  
Shale 1945  
Shale & Shells 2265  
Shale & Lime 2419  
Shale & Lime 2525  
Shale & Lime 2630  
Shale 2734  
Lime & Shale 2835  
Lime & Shale 2956  
Lime & Shale 3031  
Lime & Shale 3125  
Lime & Shale 3218  
Shale & Lime 3291  
Lime 3345  
Lime 3395  
Lime 3443  
Lime 3510  
Lime 3555  
Lime 3622  
Conglomerate 3649  
Conglomerate 3685  
Conglomerate 3716  
Arbuckle 3732  
Arbuckle 3755 T.D.

TOPS

3126 - Topeka (-959)  
3336 - Heebner (-1169)  
3356 - Toronto (-1189)  
3377 - Lansing (-1210)  
3616 - Conglomerate (-1449)  
3716 - Arbuckle (-1549)

The undersigned, GRAHAM-MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

GRAHAM-MESSMAN-RINEHART OIL COMPANY

By: J. A. Gilliland  
J. A. Gilliland

Subscribed and sworn to before me this 26th day of March, 1953.

Barbara J. Scott  
Notary Public

My commission expires: December 1, 1956

RECORDED  
STATE OF KANSAS  
3/27/53  
MAR 27 1953

CONSERVATION DIVISION  
Wichita, Kansas

**PLUGGING**  
FILE SEC 32 T 9 R 18 W  
BOOK PAGE 86 LINE 12