


15-163-00490-00-01

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rocks \_\_\_\_\_ County. Sec. 32 Twp. 9 Rge. 18 ~~(W)~~ (W)  
Location as "NE/CNW/SW" or footage from lines. SW/4 NW/4 NE/4  
Lease Owner Grant Oil Company  
Lease Name Stucky "A" Well No. 1  
Office Address 518 W K H Building, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 29 19 58  
Application for plugging filed July 6 19 58  
Application for plugging approved July 9 19 58  
Plugging commenced July 7 19 58  
Plugging completed July 11 19 58  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3756 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	160'	8 5/8	None	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set plug at 3330. Dumped sk's of cement with baler. Shot pipe lose at 1683. Pulled pipe up to 550' cul. 40 sk's of jelly mud and pumped in 20 sk's of cement. Pulled pipe on up to 150'. Pumped in 20 more sk's of cement. Pulled pipe out. Baled mud down to 40'. Dumped 10 sk's of cement up to base of cellar. Put in 10' rock bridge.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Arnett Casing Pulling Co.  
Address 172 West Third, Hoisington, Kan sas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
W. A. Grant (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) [Signature]  
W. A. Grant  
518 W K H Building, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of July, 19 58

My commission expires August 14, 1961

Ruth M. Sullivan Notary Public.  
STATE CORPORATION COMMISSION

24-2675-S 2-52-20M



15-163-00490-00-01

STUCKY #1 (WORKOVER JOB)

LOCATION: SW/4 NW/4 NE/4  
Sec. 32-98-18W  
Rooks County, Kansas  
COMMENCED: 6-18-58  
COMPLETED: 6-21-58

OPERATOR: Grant Oil Company  
518 W K H Building  
Wichita 2, Kansas

CONTRACTOR: Birmingham-Bartlett Drilling Co.  
300 Kaufman Building  
Wichita 2, Kansas

SURFACE CASING: 8-5/8" surface casing cemented at  
170' when hole was originally drilled  
by Graham-Messman-Rinehart Oil Co.  
in March, 1953.

OIL STRING: 5-1/2" casing cemented at 3717' with  
100 sacks cement.

LOG

Washdown to old total depth of 3760'

The undersigned, Richard Hindery, one of the partners of Birmingham-Bartlett Drilling Co., hereby certifies that the above is a true and correct log of the Workover Job on the Stucky #1.

BIRMINGHAM-BARTLETT DRILLING CO.

By

Richard Hindery  
Partner

Subscribed and sworn to before me  
this 2nd day of July, 1958.

Vivian F. Yinger  
Vivian F. Yinger, Notary Public

My commission expires November 29, 1958.

7/29/58

PLUGGING	
FILE	SEC 32 T 9 R 18W
BOOK	PAGE 113 LINE 8