

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-01588-00-00

API NUMBER TOO OLD

LEASE NAME RICHARDSON

WELL NUMBER 2

660 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 32TWP. 9 RGE. 18 (X)X(W)

COUNTY ROOKS

Date Well Completed 1-1-60

Plugging Commenced 12-13-90

Plugging Completed 12-13-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR R P NIXON OPERATIONS INC

ADDRESS 207 W 12TH HAYS KS 67601

PHONE# (913) 628-3834 OPERATORS LICENSE NO. 5252

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-13-90 (date)

by HAYS DALE BALTHAZOR (KCC District Agent's Name).

Is ACO-1 filed? TOO OLD If not, is well log attached? YES

Producing Formation ARBUCKLE Depth to Top _____ Bottom _____ T.D. 3705

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
SURFACE		SURF	220	8 5/8	220	NONE
PRODUCTION		SURF	3699	5 1/2	3699	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set
DOWN ANNULUS OF 8 5/8" CSG AT 400#'s MAXIMUM PRESSURE. MIXED 3SX HULLS WITH 100 SX CEMENT AND SHUT IN AT 200#'s. DOWN 5 1/2" CASING RAN TBG TO 3110' AND SPOTTED 125SX CEMENT WITH 1SX HULLS, PULLED TBG TO 1600' AND MIXED 90SX CEMENT WITH 2SX HULLS & CIRCULATED CEMENT TO SURFACE, PULLED TBG TIED ONTO CSG, PRES.
(If additional description is necessary, use BACK of this form.)
TO 800#'s W/25SX CEMENT & SHUT IN @ 700#'s.

Name of Plugging Contractor JAY-LAN CORPORATION License No. 5128


Address 207 W 12TH, HAYS KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R P NIXON OPERATIONS INC

STATE OF KANSAS COUNTY OF ELLIS, ss. DAN A NIXON

DAN A NIXON (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dan A Nixon PRESIDENT
(Address) 207 W 12TH, HAYS KS 67601



SUBSCRIBED AND SWORN TO before me this 11TH day of JANUARY, 1991

Lorna M Herrman
Notary Public
Lorna M Herrman

My Commission Expires: 6-19-92