

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rooks County, Sec. 32 Twp. 9 Rge. 18 (E) W (W)

T - 9 NORTH R - 18W

Location as "NE/CNW/SW" or footage from lines C SW NE

Lease Owner Frank J. Black

Lease Name Stuckey Well No. 2

Office Address McPherson, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 4-2-59 19

Application for plugging filed 9-10-63 19

Application for plugging approved 9-11-63 19

Plugging commenced 9-17-63 19

Plugging completed 9-25-63 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3699 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	215'	None
				5-1/2"		
				5-1/2"	3694'	2824'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3699', sanded hole to 3685' and dumped 5 sacks of cement @ 3685' with dump bailer. Pulled 5 1/2" casing to 320' and circulated with 18 sacks of gel. mud. Pumped 20 sacks of cement @ 320'. Pulled balance of 5 1/2" casing and pumped 10 sacks of cement from 30' to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
10/11/63
OCT 17 1963

PLUGGING COMPLETE.

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY License No. 436
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss. Noel J. Knight (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 7th day of October, 1963

My commission expires May 20, 1964 Milton J. Volin Notary Public.

15-163-1A294-00-00


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- GRANT OIL CO. ET AL
Farm- Stucky No. 2

SEC. 32 T. 9 R.13W
C SW NE

Total Depth. 3699'
Comm. 3-23-59 Comp. 4-2-59
Shot or Treated.
Contractor. Honaker-Davis Drilg.
Issued. 1-2-61

County Rooks
KANSAS



Elevation. 2169' RB

Production. 25 BOPD

Figures Indicate Bottom of Formations.

top soil & clay	72
sandy clay	77
clay & shale	215
shale & shells	1035
sand	1210
shale w/sand streaks and red bed	1535
Anhydrite	1570
shale & red bed	1885
shale, lime, shells	1980
lime & shale	3544
lime	3581
lime & chert	3650
chert & shale	3690
sand & chert	3699 RTD
Total Depth	

TOPS: SCOUT	
Topeka	3127
Heebner	3343
Toronto	3367
Kansas City	3386
Base Kansas City	3599
Conglomerate	3616
Upper Simpson Dolomite	3678
Lower Simpson Dolomite	3694

RECEIVED
STATE CORPORATION COMMISSION
10/11/63
OCT 11 1963
CONSERVATION DIVISION
Wichita, Kansas