

15-163-19042-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

ROOKS County. Sec. 1 Twp. 9S Rge. 19 (X) (W)
Location as "NE/CNW%SW%" or footage from lines NW SE SE
Lease Owner PETROLEUM, INC.
Lease Name GICK "D" Well No. 1
Office Address ROUTE 2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed MAY 18 19 64
Application for plugging filed MAY 18 19 64
Application for plugging approved MAY 18 19 64
Plugging commenced MAY 18 19 64
Plugging completed MAY 18 19 64
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONES

If a producing well is abandoned, date of last production - 19 -
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ELDON PETTY, HAYS, KANSAS
Producing formation - Depth to top - Bottom - Total Depth of Well 3195 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	209'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from - feet to - feet for each plug set.

MUDDERED UP WITH HEAVY MUD THRU DRILL PIPE FROM 3195 TO 550', FOLLOWED BY A WOODEN PLUG AND 20 SACKS CEMENT, MUDDERED UP WITH HEAVY MUD TO 200' FOLLOWED BY A WOODEN PLUG AND 20 SACKS CEMENT. MUDDERED UP WITH HEAVY MUD TO 40', FOLLOWED BY A WOODEN PLUG AND 10 SACKS CEMENT TO BASE OF CELLAR.

RECEIVED
STATE CORPORATION COMMISSION
5/26/64
MAY 26 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GARVEY DRILLING COMPANY
Address ROUTE #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
MONTE CHADD (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) MONTE CHADD, DIST. PROD. SUPT.
ROUTE #2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 25 day of MAY, 19 64

My commission expires SEPTEMBER 23, 1967

Notary Public.

WELL LOG 15-163-19042-00-06

COMPANY Petroleum, Inc.

SEC. 1 T. 9S R. 19W

FARM Gick

NO. D-1

LOC. NW SE SE


TOTAL DEPTH 3195'

COUNTY Rooks

COMM. 5-12-64

COMP. 5-18-64

CONTRACTOR Garvey Drilling Company



CASING 8 5/8" @ 209' w/175 sx

ELEVATION 2009' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

45' Soil and Post Rock
90' Shale and Sand Streaks
209' Blue Shale
560' Shale
1390' Sand and Shale
1444' Shale
1469' Anhydrite
1750' Shale
1880' Shale and Shells
2162' Shale and Lime
2350' Lime and Shale
2470' Shale w/Lime Streaks
2598' Shale and Lime
2725' Lime and Shale
2860' Lime
2980' Lime and Shale
3195' Lime
3195' RTD

RECEIVED
STATE CORPORATION COMMISSION
5/26/64
MAY 26 1964

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Barton } ss

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Gick D-1 well.

Sam N. Stephens

Subscribed and sworn to before me this 22nd day of May 19 64

My Commission Expires: September 23, 1967

Edward C. Guerin
NOTARY PUBLIC