


15-163-19043-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rooks County. Sec. 1 Twp. 9S Rge. 19W (E) (W)
Location as "NE/CNW/SW" or footage from lines NW NE SW
Lease Owner Lawrence Supply Company
Lease Name Gick "B" Well No. 1
Office Address Box 448 - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed April 30 19 52
Application for plugging filed June 5 19 56
Application for plugging approved June 6 19 56
Plugging commenced June 5 19 56
Plugging completed June 21 19 56
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3460 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	200'	None
				5-1/2"	3457'	2637'
				Lane Wells plug set at 3215'. Pipe perforated 3192' to 3200'.		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled the hole with sand from 3215' to 3180' and ran 4 sacks of cement. Pumped in mud and set a 10' rock bridge at 200'. Ran 15 sacks of cement at 190'. Mudded the hole to 40', set a 10' rock bridge and ran 10 sacks of cement to fill to base of cellar. Plugging completed.

Name of Plugging Contractor West Supply Co., Inc. (If additional description is necessary, use BACK of this sheet)
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. _____ (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) LAWRENCE SUPPLY COMPANY
Lawrence, Box 448, Great Bend, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 27 day of June, 1956
Jean Rebin
Notary Public.

My commission expires October 1, 1958

24-7366-S 3-53-20M

6/28/56

PLUGGING
FILE SEC. 1 T 9 R 19W
BOOK PAGE 67 LINE 44

15-163-19043-00-00

B & R Drilling, Inc.
Gick "B" #1

NW NE SW of Sec. 1-9-19
Rooks County, Kansas

Total Depth: 3460'
Comm. 4/11/52
Comp. 4/27/52

Casing

8 5/8" Set @ 200
5 1/2" Set @ 3457

3W HN 1/2 W
Platinum

Cement

130 sacks Lone Star
100 sacks Lone Star

Formation

Depth

Shale-sand-shells	199
Shale-shells	560
Sand-shells	600
Shale-shells	1210
Shale-red bed	1420
Anhydrite	1445
Shale-shells	1630
Shale-lime	3199
Lime	3232
Line-shale	3277
Lime	3460'

STATE OF KANSAS }
 } SS
RUSSELL COUNTY }

I hereby certify that the above information is true and correct to the best of my knowledge.

Carla Betty

Subscribed and sworn to before me this 1st day of May, 1952.

Notary Public

My commission expires: 6-17-54.

PLUGGING			
FILE	SEC. 1	T 9	R 19W
BOOK	PAGE 67	LINE 44	

6/5/56
MISSION
DIVISION