

15-163-19302 -00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD

Rooks

County, Sec. 2 Twp. 9 Rge. 19 (E) W (W)

Location as "NE/CNW/SE" or footage from lines. App. S/2 S/2 S/2 SE

Lease Owner Continental Oil Co.

Lease Name Barry L.K.C. Unit Well No. 622

Office Address Box 267 Great Bend, Kansas 67530

Character of Well (completed as Oil, Gas or Dry Hole) Water Supply Well

Date well completed 19

Application for plugging filed 19

Application for plugging approved July 13 19 77

Plugging commenced Nov. 5 - 9:00 AM 19 77

Plugging completed Nov. 5 - 10:00 AM 19 77

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Cedar Hill Depth to top 885 Bottom 1105 Total Depth of Well 1412 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	253'	10 3/4	253	0
		0	1410'	7 "	1410	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pumped 3 sacks Hulls - 100 sacks cement - 15 sacks gel

Rubber plug - 50 sacks cement. Max press 1000 # shot in press. 1000#.

Cement from 1105' to 800'

Gel and water from 800' to 240'

Cement from 240' to 3' below surface

Received  
11/30/77

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Continental Oil Company

Address Box 267, Great Bend, Kansas 67530

STATE OF Kansas

COUNTY OF Barton, 53.

Hugh S. Miles

well, being duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 30 1977

(Signature)

Box 267, Great Bend, Kansas 67530

(Address)

CONSERVATION DIVISION  
Wichita, Kansas

My commission expires June 28, 1978

Notary Public.

# WELL LOG

15-163 19302 -00-00

COMPANY Continental Oil Company

SEC. 2 T. 9S R. 19W

FARM Barry Lansing-Kansas City No. Unit 622

LOG. 162' FSL & 1408' FEL

TOTAL DEPTH 1412'


COUNTY Rooks

COMM. 4-26-67

COMP. 4-28-67

CONTRACTOR Garvey Drilling Company

CASING 10 3/4" @ 253' w/200 sx  
7" @ 1410' w/500 sx



ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

60' Top Soil and Post Rock  
518' Shale  
575' Sand  
655' Shale with Sand  
714' Shale  
815' Sand  
1403' Shale  
1412' Anhydrite  
1412' RTD

7/13/77  
JUL 15 1977  
DIVISION  
Rocks

File  
State Corp. Comm.  
Kansas Geological Society

State of Kansas  
County of Barton } ss

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Barry Lansing-Kansas City Unit No. 622 well.

Subscribed and sworn to before me this 10th day of May 19 67

My Commission Expires: November 5th, 1969

Sam N. Stephens  
Richard A. Boep  
NOTARY PUBLIC