

15-163-19301-00-01

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-D21843

LEASE NAME Barry SWD System

WELL NUMBER D-07

330 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 2 TWP. 9 RGE. 19 (E) or (W)

COUNTY Rooks

Date Well Completed 09-26-47

Plugging Commenced 08-12-89

Plugging Completed 08-12-89

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Phillips Petroleum Company

ADDRESS Route 3, Box 20-A, Great Bend, Kansas 67530

PHONE# (316) 793-8421 OPERATORS LICENSE NO. 5229

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 08-12-89 (date)

by Dennis L. Hamel (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Disposal ~~FORMATION~~ Formation Arbuckle Depth to Top 3442' Bottom 3858' T.D. 3702'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From Surf	To	Size	Put in	Pulled out
LKC	Oil & Water	Surf	200	10 3/4"	200	0
		Surf	3443	7"	3443	0
		Surf	3413	4 1/2"	3413	0
Arbuckle	Oil & Water					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. MI rig. Cleaned out tubing to 1600'. RU perforators. Perforated tubing-casing at 1400' and 900'. RIH w/1" tubing, spot 50 sks common cmt on bottom. Pull up to 600' w/1" tubing. Circulated cmt to surface. Pulled 1" tubing, 50 sks 60/40 Pozmix 6% gel. Hooked up to 4 1/2" casing, sq add 300 sks 60/40 Pozmix gel. Max psi 300#, SI 150#. Cmt circ annulus. 4 1/2" csg hooked up 10 3/4"  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Phillips Petroleum Company License No. 5229

Address Route 3, Box 20-A, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Phillips Petroleum Company

STATE OF Kansas COUNTY OF Barton, ss.

J. W. Taylor (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) J. W. Taylor

(Address) Route 3, Box 20-A, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 10th day of October, 19 89

Carla M. Yahnke  
Notary Public

My Commission Expires: 10-23-92



s.p. and sq 0 sks cmt. Max 1400# psi.