

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 16 1963
 9-16-63
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Earl Mabry of Cities Service Oil Co. has this

date requested permission to plug the following described well:

Mr. Mabry guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company,

Complete Address: Box # 533, Russell, Kansas.

Lease Name: Seefeld Well No. 6

Location: NW-SW-NE Sec. 18 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3843 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Mabry was instructed to plug the well as follows:

240'--8 5/8" Surface pipe, cement circulated with 175 Sx.

3840'--5 1/2" cemented with 175 Sx. 5 1/2" Squeezed @ 1238' with 250 Sx.

Sand well back from TD to 3818' and set 2 Sx cement with dump bailer.

Set bridge @ 600' and 10 Sx cement thru tubing.

Set plug @ 240' and displace 10 Sx cement thru tubing.

Set plug @ 35' and 5 Sx cement to bottom of cellar.

Very truly yours,

H. A. Nichols
 Conservation Division Agent