

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
12-20-71  
DEC 20 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Millard Lindsay of Cities Service Oil Company has this date requested permission to plug the following described well:

Mr. Lindsay guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company,

Complete Address: Box #553, Russell, Kansas.

Lease Name: Seefeld Well No. A-5

Location: SE-NE-NE Sec. 18 Twp. 9 Rge. (E)(W) 21

County: Graham Total Depth 3784' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Lindsay was instructed to plug the well as follows:

240'--8 5/8" Surface casing, cement circulated with 175 Sx.  
3779'--5 1/2" Production casing cemented with 175 Sx. No plug back nor perforations indicated.

Sand well back to 3760' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

W. L. Dickel  
Conservation Division Agent