

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 21 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Ray Blandin of Cities Service Oil Company has this date requested permission to plug the following described well:

Mr. Blandin guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company,

Complete Address: Box #553, Russell, Kansas.

Lease Name: Seefeld Well No. X A-7

Location: CNW-NE-NE Sec. 18Twp. 9 Rge. (E)(W) 21

County: Graham Total Depth 3784 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Blandin was instructed to plug the well as follows:

280'--8 5/8" Surface casing, cement circulated with 275 Sx.  
3780'--5 1/2" Production casing cemented on bottom with 175 Sx. 5 1/2" has been  
squeezed @ 1237' with 176 Sx. cement. No plug back, no perforations.

Squeeze 5 1/2" with 1 sack hulls, 30 sacks gel and and 102 Sx. cement,  
staged.

Very truly yours,

Conservation Division Agent