



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 1 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Walter Voth of Knight Casing Pulling Co., Inc. has this date requested permission to plug the following described well:

Mr. Voth guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Company, Incorporated,

Complete Address: 1425 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Karst Well No. 1

Location: NE-SW-NW Sec. 29 Twp. 9 Rge. (E)(W) 21

County: Graham Total Depth 3878' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Voth was instructed to plug the well as follows:

234'--8 5/8" Surface casing, cement circulated with 160 Sx.
3873'--5 1/2" Production casing cemented on bottom with 150 Sx. No Plug-
back nor Perforations indicated.

Sand well back to 3850' and set 5 Sx. cement with dump bailer. Pull 5 1/2"
casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft.
cement, staged.

Very truly yours,

H. L. Oriskany
Conservation Division Agent