

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
3/3/64
MAR 3 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Glenn Hall of Knight Casing Pulling Co. has this
date requested permission to plug the following described well:
American Petrofina Co. of Texas.
Mr. Hall guarantees payment of the plugging fee.

Operator's full Name: American Petrofina Company of Texas,

Complete Address: Box #209, Russell, Kansas.

Lease Name: Ford Well No. 1

Location: SE-SE-SE Sec. 29 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3915 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hall was instructed to plug the well as follows:

255'--8 5/8" Surface pipe, cement circulated.
3911'--5 1/2" Production casing cemented with 75 Sx.

Sand well back to 3900' and set 5 Sx. cement with Dump Bailer.
Pull 5 1/2" to 600' and circulate heavy gel mud. Pull 5 1/2" to 540'
and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 240' and dis-
place 20 Sx. cement thru 5 1/2". Pull 5 1/2", set rock bridge @ 35'
and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Nichols