



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 7/31/63
 JUL 31 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Ben Kelley of Shallow Water Refining Co. has this date requested permission to plug the following described well:

Mr. Ben Kelley guarantees payment of the plugging fee.

Operator's full Name: Shallow Water Refining Company,

Complete Address: 542 Petroleum Building, Wichita, Kansas.

Lease Name: Harrold Well No. 2

Location: CN $\frac{1}{2}$ -N $\frac{1}{2}$ -SW Sec. 29 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3890 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Kelley was instructed to plug the well as follows:

181'--8 5/8" Surface pipe, cement circulated. 3885'--5 1/2"
casing cemented with ??? Sx. 5 1/2" squeezed in the Dakotas
to top of surface.-----Sand back to 3850' and set 5 Sx cement
with dump bailer. Find fluid level, set bridge and 5 Sx cement.
Set bridge @ 230' and 20 Sx cement. Mud to 30' and 5 Sx cement
to bottom of cellar.

Very truly yours,

H. L. Nichols
 Conservation Division Agent