

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
11/8/65
NOV 8 1965

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. T.J Buffington of Red Tiger Drlg Co has this

date requested permission to plug the following described well:

Mr. Buffington guarantees payment of the plugging fee.

Operator's full Name: Mayfield Smith

Complete Address: ⁹²⁸ Union Center, Wichita Kansas

Lease Name: Eichman Well No. 1

Location: NW NW SE Sec. 30 Twp. 9 Rge. 21 (E)(W)

County Graham Total Depth 3940 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Buffington was instructed to plug the well as follows:

Jett pits circulate hole with heavy mud, set cementing plug at 540'

and displace 20 sax cement thru drill pipe, heavy mud to 200', set

cementing plug and displace 20 sax cement, heavy mud to 40' set

cementing plug, 1/2 sac hulls and ten sax cement, cementing to base of cellar.

Very truly yours,

Gilbert P. Leiker
Conservation Division Agent