

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
9/26/66
SEP 26 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Johnnie Crowe of Garvey Drilling Co., has this date requested permission to plug the following described well:

Mr. Crowe guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Incorporated,

Complete Address: 300 West Douglas, Wichita, Kansas.

Lease Name: Smith "AL" Well No. 1

Location: NW-SE-NW Sec. 30 Twp. 9 Rge. (E)(W) 21

County Graham Total Depth 3924 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Crowe was instructed to plug the well as follows:

215'--8 5/8" Surface pipe, cement circulated with 175 Sx.

Circulate hole with heavy mud, set plug @ 540' and 20 Sx. cement.

"	"	210' with 1/4 sk. hulls & 20 Sx. cement.
"	"	40' with 1/2 sk. hulls & 10 Sx. cement.

Very truly yours,

Conservation Division Agent