

State of Kansas



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 12 17 1968  
 DEC 17 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Bill Walker of Rains & Williamson Oil Co. Inc. has this date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Company, Incorporated,

Complete Address: 1425 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Eichman Well No. 1

Location: SE-NE-NW Sec. 32 Twp. 9 Rge. (E)(W) 21

County: Graham Total Depth 3925 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

217'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 700'.

Circulate hole with heavy mud. Pull DP to 800' and displace 100 Sx.  
cement thru D<sup>2</sup>. Pull DP to 240' and displace 20 Sx. cement thru DP.  
Pull DPm set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

*M. G. Saffels*

Conservation Division Agent