

15-065-0114-00-00

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Rhyne of Ralph R. Rhyne has this  
date requested permission to plug the following described well:

Mr. Rhyne guarantees payment of the plugging fee.

Operator's full Name: Ralph R. Rhyne,

Complete Address: Box #385, Russell, Kansas.

Lease Name: Eichman Well No. 1

Location: NE-NE-NE Sec. 32 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3918 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Rhyne was instructed to plug the well as follows:

220'--8 5/8" Surface pipe, cement circulated with 150 Sx.  
3912'--5 1/2" Production casing cemented with 100 Sx. on bottom, DV tool  
@ 1840' with 450 Sx. cement circulated.

Sand well back to 3860 and set 5 Sx. cement with dump bailer. Push  
plug to 1500' and sand back to 1440' and set 5 Sx. cement with dump  
bailer. Check hole for fluid under 24 hours, if none above plug fill  
hole with Redi-mix cement.

SEP 15 1967  
9/15/67  
CONSERVATION DIVISION  
Wichita, Kansas

Very truly yours,

H. L. DeChale  
Conservation Division Agent