

15-163-23179-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

RECEIVED  
STATE CORPORATION COMMISSION  
10/2/91  
OCT 02 1991

**WELL PLUGGING APPLICATION FORM**  
(File One Copy)

CONSERVATION DIVISION  
Wichita, Kansas

API NUMBER 15-163-23,179-00-00 (of this well) (This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Energy Exploration, Inc. OPERATOR'S LICENSE NO. 5063

ADDRESS 1002 S. Broadway, Wichita, KS 67211 PHONE # (316) 267-7336

LEASE (FARM) Pywell WELL NO. #1 WELL LOCATION 2250'FNL 1050'FWL COUNTY Rooks

SEC. 26 TWP. 9S RGE. 19 (E) or (W) TOTAL DEPTH 3700' PLUG BACK TD \_\_\_\_\_

**Check One:**

OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ D & A X SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8" SET AT 214' CEMENTED WITH 60-40 posmix-160 sx SACKS

CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

PERFORATED AT \_\_\_\_\_

CONDITION OF WELL: GOOD X POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING Fill w/heavy mud; set 1st plug @ 3620' w/25 sx; 2nd plug @ 1550' w/25 sx; 3rd plug @ 925' w/100 sx; 4th plug @ 265' w/40 sx; ; 5th plug @ 40' w/wiper plug w/10 sx; rathole 15 sx; 215 sx 60-40 posmix 6% gel 1/4# Floccel per sx.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? \_\_\_\_\_ IS ACO-1 FILED? No  
(If not explain.) Sent to Operator to complete.

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 1:45 p.m. 9-3-91

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harold Maley PHONE # (913) 674-5768

ADDRESS 216 E. McFarland, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie RTD, Inc. LICENSE NO. 30684

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack R. Wharton  
(Operator or Agent)

DATE: October 1, 1991