

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 01697-00-00 15-163-97651 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR OXY USA INC. KCC LICENSE # 5447
(owner/company name) (operator's)

ADDRESS 110 S. Main #800 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 265-5624

LEASE Bullock ^{KCC} ~~247~~ WELL# 1 SEC. 27 T. 9 R. 19 (East West)

C - NE - NE - SW SPOT LOCATION/QQQQ COUNTY Rooks

330 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

330 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL X GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8-5/8" SET AT 315' CEMENTED WITH 175 sx SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 3661' CEMENTED WITH 150 sx SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 9 Shots @ 3638-46, 22 Shots @ 3644-48

ELEVATION 2207' / T.D. 3661' PBSD 3348' ANHYDRITE DEPTH
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD X POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING As per KCC requirements.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED?

If not explain why? Not required when well was completed.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

J.D. Hininger PHONE# (913) 434-7681

ADDRESS Drawer D City/State Plainville, KS 67663

RECEIVED
KANSAS CORP COM
3/11/96
1996 MAR 11 A 9:41

4)

PLUGGING CONTRACTOR Express Well Service* / Allied Cemeting KCC LICENSE # 6426* ^{6/96}
(company name) (contractor's)
ADDRESS P.O. Box 426 Victoria, KS* PHONE # (913) 735-9405

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) _____

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 3/4/96 AUTHORIZED OPERATOR/AGENT: Timothy J. Voss Timothy J. Voss
(signature)

RECEIVED
KAISAS CORP CORN
1996 MAR 11 A 9:42

WELL RECORD

Company Cities Service Oil Co. Well No. 1 Farm Bullock
 Location 330' South and 330' West of Center Sec. 27 T. 9 R. 19W
 Elevation 2209 (2207 Gr.) County Hooks State Kansas
 Drlg. Comm. March 30, 1948 Contractor R. W. Rine Drilling Company
 Drlg. Comp. April 8, 1948 Acid 500 gals. 4-14-48
 T. D. 3661'; P.B. 3657' Initial Prod Physical Potential: 50l oil, no water, 24 hrs. (4-17-48)

CASING RECORD:

8-5/8" ○ 315' cem. 175 sx cem. and
 200# C. C.
 5-1/2" ○ 3661' cem. 150 sx cem.

FORMATION RECORD:

clay & sand	0-210
shale & shells	690
shale & sand	800
shale & shells	1060
sand	1125
shale & shells	1565
anhydrite	1607
shale & shells	2195
lime & shale	2355
shale & lime	2465
lime & shale	2695
shale & lime	2775
lime & shale	2960
shale & lime	3025
shale & shells	3170
lime & shale	3309
lime	3632-
conglomerate	3647
lime	3667

3667 dot. TD = 3661 SLM

Corr. Top Lansing	3368'
Corr. Top Conglomerate	3627'
Corr. Top Eros. Arbuckle	3636'
Corr. Top Arbuckle	3642'
Penetration	19'
Total Depth	3661'
Perf. Pen. Arbuckle	6'

Drilled cement to 3657 SLM.

Perf. 9 shots 3638-46
 " 22 shots 3644-48

60' mud and oil in 30 mins.,
 bailed dry; 80' mud and oil in
 35 mins.

Bailed 2 bbls. oil per hr./12 hrs.

SYFO:	550'	2°
	1200'	1°
	1500'	1°
	2000'	1°
	2500'	1°
	3000'	1°
	3450'	0°

7-7/8" rotary hole.

RECEIVED
 KANSAS CORP COMM
 1948 MAR 11 A 9:42



Kansas Corporation Commission

Bill Graves, Governor Susan M. Seltsam, Chair F.S. Jack Alexander, Commissioner Timothy E. McKee, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

March 14, 1996

OXY USA Inc
110 S Main #800
Wichita KS 67202

^{KCC 2410}
Bullock "A" #1
API 15-163-N/A
330 FSL 330 FWL
Sec. 27-09S-~~05W~~19W
Rooks County

Dear J.D. Hininger,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #4
2301 E 13th
Hays KS 67601
(913) 628-1200