

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____
LOCATION NW NW SE
SEC. 29 TWP. 9 RGE. 21

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. B-1 Lease Wichman

Operator K & E Drg Co Inc. Address 719 N. Boston Wichita, Kans

Field _____ County Graham

Total Depth 3940 Feet.

Plugging Contractor same

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 250' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug at

550', displaced 20 sax cement through drill pipe, heavy mud to

200', set cementing plug and displaced 20 sax cement through drill

pipe, heavy mud to 40', set cementing plug, 1/2 sack hulls and 10 sax

cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
10/5/57
OCT 5 - 1957

CONSERVATION DIVISION
Wichita, Kansas

Edwin Petty

District Conservation Agent

Date 10-2-57

PLUGGING
FILE SEC. 29 T. 9 R. 21W
BOOK PAGE 51 OF 42