

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
12/4/67
DEC 4 1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Allison and Black,
Complete Address 1415 Plaza Building, Wichita, Kansas.
Lease Name Smith Well No. A-1
Location NE-SW-NW Sec. 30 Twp. 9 Rge. (E) (W)21
County Graham Total Depth 3915'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor B. and B Drilling, Incorporated,

Address 548 Petroleum Building, Wichita, Kansas. License No. _____

Operation Completed: Hour 1:15 AM Day 27 Month 11 Year 1967

The above well was plugged as follows:

208'--8 5/8" Surface pipe, cement circulated with 150 Sx.
Dakota section from 1030' to 1225'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 100 Sx. cement thru
DP from 1250' to 930'. Pulled DP to 240' and displaced 25 Sx. cement thru DP from
240' to 165'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement from
bridge to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

UNVOICED

Signed: M. L. Dinkel
Well Plugging Supervisor

DATE 12/5/67
INV. NO. 6828-U