

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SE NE NE

SEC. 32 TWP. 9 RGE. 21 *w*

Dry Hole x Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Eichman

Operator Skelly Oil Co Address Russell, Kans

Field \_\_\_\_\_ County Graham

Total Depth 3965 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 377' circulated with cement.

~~Filled with~~ Pumped in 25 sax cement on bottom through drill  
pipe, filled with rotary mud to 377', set Halliburton plug and  
pumped in 25 sax cement through drill pipe, filled with  
rotary mud to 75', set Halliburton plug and filled to bottom  
cellar with 25 sax cement.

5/25/50

**PLUGGING**  
FILE SEC 32 TWP. 9 RGE. 21  
BOOK PAGE 7 LINE 20

*J. J. [Signature]*  
District Conservation Agent

Date 5-23-50