

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
11/22/71  
NOV 22 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name National Oil Company,  
Complete Address 200 West Douglas, Wichita, Kansas.  
Lease Name Eichman Well No. 1  
Location CN/2-SW-NE Sec. 32 Twp. 9 Rge. (E) (W) 21  
County Graham Total Depth 3968'  
Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X  
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Murfin Drilling Company,  
Address 617 Union Center Building, Wichita, Kansas. License No. \_\_\_\_\_  
Operation Completed: Hour 7:30 PM, Day 19 Month 11 Year 1971

The above well was plugged as follows:

202'--8 5/8" Surface casing, cement circulated with 135 Sx.  
Top of Dakota section @ 725'.

Circulated hole with heavy mud. Pulled DP to 950' and displaced 100 Sx. cement thru  
DP from 950' to 625'. Pulled DP to 310' and displaced 25 Sx. cement thru DP from  
310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *K. L. Nichols*  
Well Plugging Supervisor

INVOICED

DATE 11-29-71  
INV. NO. 4698-W