

*Y*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 17 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Rains & Williamson Oil Company, Incorporated,

Complete Address: 1425 Wichita Plaza Building, Wichita, Kansas.

Lease Name Eichman Well No. 1

Location SE-NE-NW Sec. 32 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3925'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 10:00PM Day 13 Month 12 Year 1968

The Above well was plugged as follows:

217'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 700'.

Circulated hole with heavy mud. Pulled DP to 800' and displaced 100 Sx. cement thru  
DP from 800' to 575'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from 240'  
to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of  
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Nichols*  
Well Plugging Supervisor

DATE 12/17/68  
INV. NO. 9031-W