

KANSAS



STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Ralph R Rhyne,

Complete Address: Box #385, Russell, Kansas.

Lease Name Eichman Well No. 1

Location NE-NE-NE Sec. 29<sup>32</sup> Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3918'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Above

Address:        License No.       

Operation Completed: Hour 11:00AM Day 011 Month 9 Year 1967

The Above well was plugged as follows:

220'--8 5/8" Surface pipe, cement circulated with 150 Sx.

3912'--5 1/2" Production casing cemented with 100 Sx. on bottom, DV tool set @ 1840' with 450 Sx. cement circulated.

Sanded well back to 3858' and set 5 Sx. cement with dump bailer. Pushed plug to 1500'

and sanded well back to 1440' then set 5 Sx. cement with dump bailer, let cement set

and filled hole to cellar with Redi-Mix cement using 7 yards.

I hereby certify that the above well was plugged as herein stated.

INVOICED

SEP 15 1967  
9/15/67

Signed: [Signature]  
Well Plugging Supervisor

DATE 9/15/67  
INV. NO. 6342-W

CONSERVATION DIVISION  
Wichita, Kansas