

State of Kansas



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Larry Hicks of Kandrilco has this date requested permission to plug the following described well:

Operator's Full Name: Petro-Dynamics L.T.O.

Complete Address: 555 N. Woodlawn Bldg 1, Suite 207, Wichita, Ks. 67208

Lease Name: Fleming Well No. 1

Location: CNW-NW-SE Sec. 1 Twp. 9 Rge. 19 (E) (W)

County: Rock Total Depth: 3500

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Hicks was instructed to plug the well as follows:

8 5/8 @ 264' w/180 ox common 2% gel 3% cc (allied)  
Ordered 135 ox 5% so permix 1% gel - 3% cc + 8 5/8 plug  
Spotted 70 ox @ 300'  
" 40 ox @ 260'  
" 10 ox @ 40'-0' on solid bridge  
" 10 ox in rat hole  
" 5 ox in mouse hole  
Circ heavy mud between all plugs

Very truly yours,

Dennis L. Hancock  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION  
5/17/82  
MAY 17 1982  
CONSERVATION DIVISION  
Wichita Kansas