



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
2/19/70
FEB 19 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Mason of Dunne-Gardner has this date requested permission to plug the following described well:

Mr. Mason guarantees payment of the plugging fee.

Operator's full Name: Black Petroleum, Inc.

Complete Address: 200 W. Douglas Wichita, K.S.

Lease Name: Fywell Well No. 1

Location: SE SE SW Sec. 26 Twp. 9 Rge. (E)(W) 19

County: Rooks Total Depth 3437 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Mason was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 685' and displace
70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo J. Massey
Conservation Division Agent