

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
11/5/73
NOV 5 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Clinton Oil Company

Complete Address 217 N. Water Wichita, Kansas 67202

Lease Name Frank Cerrow Well No. 5

Location SW NW NE Sec. 23 Twp. 9 Rge. (E) (W) 19

County Rooks Total Depth 3515'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Pipe Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 4 P Day 1 Month 11 Year 1973

The above well was plugged as follows:

Total Depth 3515' 8 5/8 csg set at 196' cwc 150 sk.

5 1/2 csg set at 3510' cw 100 sk cem.

5 1/2 csg DV tool set at 1472' cwc 500 sk. Top of cem. 497'.

NO pipe recovered.

Pumped down annulus (8 5/8 x 5 1/2) with 25 sk cem.

Pumped down 5 1/2 csg with 25 sk cem. -- 30 sk gel & water W/400 lbs hulls -- released

5 1/2 plug and pumped 50 sk cem.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/5/73

INV. NO. 8122-4

Signed: Leo F. Messerly
Well Plugging Supervisor