

15-163-01680-06-00



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
12/26/73
DEC 20 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Clinton Oil Company

Complete Address 217 N. Water, Wichita, Kansas 67202

Lease Name Frank Cerrow Well No. 6

Location SW NE NE Sec. 23 Twp. 9 Rge. (E) (W) 19

County Becks Total Depth 3540'

Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Co. Teels

Address _____ License No. _____

Operation Completed: Hour 10:30 A Day 22 Month 12 Year 1973

The above well was plugged as follows:

Total Depth 3540' 8 5/8 esg set at 193' ewe 150 sk.

5 1/2 esg set at 3536' ew 150 sk cem.

5 1/2 esg 2-stage at 1518' ewe 500 sk. No pipe recovered.

Pumped down 5 1/2 esg with 25 sk emt - 30 sk gel & water W/400 lbs hulls - released

5 1/2 plug and pumped 50 sk emt W/100 lbs hulls. Max PP 1000# SIP 1000#

Pumped down annulus (8 5/8 x 5 1/2) with 25 sk cem. SIP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Muesy
Well Plugging Supervisor

INVOICED

DATE 12/28/73

INV. NO. 8328-W