

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 35-20  
LOCATION NE NW NE  
SEC. 23 TWP. 9 RGE. 19

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 3 Lease Gerrow  
Operator Stanolind Oil & Gas Address Gorham, Kans  
Field \_\_\_\_\_ County Rooks  
Total Depth 3555 Feet.

(Describe briefly the manner in which the well was plugged)

13" at 158' circulated with cement - 5 1/2" at 3513' with  
100 sax cement behind.

Filled with chat to 3500', set 4 sax cement with dump  
bailer, pulled 2715' 5 1/2", filled hole with heavy mud to  
158', set rock bridge and 25 sax cement, filled with mud  
to 25', set rock bridge and 15 sax cement to bottom cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 21 1950

CONSERVATION DIVISION  
Wichita, Kansas  
District Conservation Agent

Date 11-17-50

PLUGGING  
FILE SEC 23 9 R 19W  
PAGE 35 LINE 20