

15-163-02966-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SE SE NW

SEC. 23 TWP. 9 RGE. 19W

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease \_\_\_\_\_ Cerrow 206 Union Nat'l Bk Bldg.

Operator C & G Drg Co Address Wichita, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3518 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 151' circulated with cement - 5 1/2" at 3514' with  
100 sax cement behind.

Filled with chat to 3500', set 4 sax cement with dump bailer,  
pulled 2800' 5 1/2", filled hole with mud to 151', set rock  
and 15 sax cement, mud to 35', set rock and 10 sax cement  
to bottom cellar.

**PLUGGING**  
FILE SEC 23 T 9 R 19W  
BOOK PAGE 57 LINE 14

RECEIVED  
STATE CORP COM  
11/6/52

Edw. J. [Signature]  
District Conservation Agent  
Date 11-3-52