

15-163-03424-00-00

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 115-13 County: Rooks

Location: SE SW SE Sec. 23 Twp. 9 Rge. 19 (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 3576

I have this date completed supervision of plugging of:

Lease Name: Sandion Well No. 2

Operator's Full Name: Murfin Drg Co

Complete Address: 617 Union Center Wichita, Kans

Plugging Contractor: Ace Pipe Pulling Co

Address: Great Bend, Kans License No. 2

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes  No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 6PM Day 19 Month 7 Year 58

The above well was plugged as follows:

8 5/8" at 188' circulated with cement - 5 1/2" 3561' with 50 sax cement behind - P. B. to 3540', perforated 3318'.

Filled with sand to 3300', set 4 sax cement with dump bailer, pulled 2000' 5 1/2" to 300', circulated hole with heavy mud ( 40 sax Gel), displaced 20 sax cement through 5 1/2" at 300', heavy mud to 180', set 20 sax cement through 5 1/2" at 180', heavy mud to 35', set rock and 10 sax cement to bottom cellar.

Mudding and cementing by Sun Cementing Co.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

PLUGGING  
FILE SEC 23 T. 9 R. 19W  
BOOK PAGE 115 LINE 13

STATE CORP. COM. DIVISION  
7/21/58  
JUL 29 1958  
CONSERVATION DIVISION  
Wichita, Kansas