

15-163-03508-00-00



Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
8/1/75  
AUG 1 1975  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Winona J. Bowman

Complete Address Box 37, Codell, Kansas 67630

Lease Name Jelinek Well No. 6

Location SW NE SE Sec. 23 Twp. 9 Rge. (E) (W) 19

County Rooks Total Depth 3540'

Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Southwest Casing Pulling

Address Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 11:30 A Day 31 Month 7 Year 1975

The above well was plugged as follows:

Total Depth 3540' 8 5/8 csg set 255' cwc 150 sx.

4 1/2 csg set 3536' cw 125 sx cem.

4 1/2 csg PBTD 3490' & perf. (3200-3203)

Filled 4 1/2 csg W/sd (3490-3175) dumped 3 sx cem W/dump bailer. (3157-3145)

Cutoff & recovered 1050' of 4 1/2 csg.

Pumped down 8 5/8 csg with 10 sx gel & water W/300 lbs hulls -50 sx 50-50 poz 6% -

10 sx gel & water -released 8 5/8 plug & pumped 50 sx 50-50 poz 6%. PP 250 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo D. [Signature]  
Well Plugging Supervisor

INVOICED

DATE 8/5/75

INV. NO. 1716