

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
6/16/67
JUN 16 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Four-Way Operating, Inc.,

Complete Address: Box 698 Great Bend, Kansas

Lease Name Saindon Well No. 5 A

Location NW SE SE Sec. 23 Twp. 9 Rge. 19 (E) (W) X

County Rooks Total Depth 3557'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers Inc.

Address: Box 486 Ellinwood, Kansas License No. 462

Operation Completed: Hour 4 P Day 14 Month 6 Year 1967

The Above well was plugged as follows:

Total Depth 3557' 8 5/8 csg set at 320' cwc 175 sc.

5 1/2 csg set at 3552' cw 150 sc cement.

DV tool set at 1544' and circulated to surface with 425 sc cement.

PbB 3516' and perf. 3385'

Set plug at 3350' and dumped 5 sc cement with dump bailer.

No pipe recov. Set 5 1/2 plug at 325' and filled to surface with readymix cement.

Filled annulus (5 1/2-8 5/8) to surface with readymix cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Roz. Massey
Well Plugging Supervisor

DATE 6-16-67
INV. NO. 5413-W