

15-163-03698-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
8/1/75
AUG 1 1975
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Winona J. Bowman

Complete Address Box 37, Codell, Kansas 67630

Lease Name Jelinek Well No. 1

Location NW NE SE Sec. 23 Twp. 9 Rge. (E) (W) 19

County Rooks Total Depth 3554'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 1 P Day 31 Month 7 Year 1975

The above well was plugged as follows:

Total Depth 3554' 8 5/8 csg set 281' cwc 200 sx.

5 1/2 csg set 3540' cw 100 sx cem.

Filled 5 1/2 csg W/sd (3554-3525) dumped 4 sx cem W/dump bailer. (3525-3495)

Cutoff & recovered 833' of 5 1/2 csg.

Mixed & pumped down 8 5/8 csg with 10 sx gel & water W/300 lbs hulls -50 sx 50-50

6% -10 sx gel & water -plug & 50 sx 50-50 poz 6%. PP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/5/75
INV. NO. 1715-W

Signed: Leo Messing
Well Plugging Supervisor