

15-163-19325-00-00

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

*R*

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 147-14 County: \_\_\_\_\_ Rooks

Location: SW SW SE Sec. 25 Twp. 9 Rge. 19 (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 3556

I have this date completed supervision of plugging of:

Lease Name: Sandion Well No. 4

Operator's Full Name: Murfin Drg Co

Complete Address: 617 Union Center Wichita, Kans

Plugging Contractor: Ace Pipe Pulling Co

Address: Great Bend, Knas License No. 2

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No \_\_\_\_\_

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 3PM Day 30 Month 11 Year 58

The above well was plugged as follows:

8 5/8" at 188' circulated with cement - 5 1/2" 3552' with 75 sax cement behind.

Set 5 sax cement on bottom with dump bailer - pulled 24'0' 5 1/2" to 550', circulated hole with heavy mud (Gel) through 5 1/2", displaced 20 sax cement through 5 1/2" at 550', heavy mud to 150', displaced 20 sax cement through 5 1/2" at 150', heavy mud to 35', set rock and 10 sax cement to bottom cellar.

Mudding and cementing by Sun Cementing Co.

Signed: *Edon Kelly*  
Conservation Division Agent

Reviewed: *J Lewis Brock*  
Field Supervisor

RECEIVED  
STATE CORPORATION COMMISSION  
12/9/58  
DEC 9 - 1958  
CONSERVATION DIVISION  
Wichita, Kansas

marks:

PLUGGING  
FILE SEC 23T 9 R 19W  
BOOK PAGE 147 LINE 14